W-140 Channel Improvements CIP Number T-1734



Presented to the Board of Directors February 25, 2014

W-140 Channel Improvements

- \$13 million infrastructure project
- 18 month construction schedule
- 15 acre feet of new detention
- 10 year flood event design
- 66 structures saved from flooding
- +/- 6000 LF new channel construction
- Extends from Gessner to basin



Existing Conditions

- Channel length 5,800 feet
- Channel volume 15 acre feet
- Avg. cross sectional area 102 SF
- Maintenance challenges High



Existing Conditions – Gessner Facing East



Existing Conditions – Witte Road Facing West



Existing Conditions – Witte Road Facing East



Existing Conditions – Bunker Hill Facing West



Existing Conditions – Bunker Hill Facing East



Existing Conditions – Basin Facing West



Improved Conditions

- 30 acre feet
- Preliminary Design LAN
- Detailed Design Klotz
- Enclosed box section
 - Gessner to Bunker Hill
 - Linear park
 - Low maintenance
- Open channel section
 - Bunker Hill to basin











ALTERNATE E: STORM SEWER BOX ENCLOSURE



Water Surface Elevation Reductions

	10 -	Year	100 – Year		
	WSEL Reduction In Channel	WSEL Reduction In Neighborhood	WSEL Reduction In Channel	WSEL Reduction In Neighborhood	
Phase 1	-0.7	-1.0	-0.6	-0.4	
Phase 2	-2.5	-1.1	-2.1	-0.7	
Phase 3	-2.2	-2.8	-1.7	-1.1	

Authority Letters from USACE and HCFCD



site (see attached map) does not contain waters of the United States. Therefore, any work, structures, or the discharge of fill material on the project site is not subject to Section 10 of the Rivers and Harbors Act or Section 404 of the Clean Water Act (CWA) and does not require a Department of the Army permit.

This determination has been conducted to identify the limits of the Corps' Clean Water Act jurisdiction for the particular site identified in this request. This determination may not be valid for the wetland conservation provisions of the Food Security Act of 1985, as amended. If you or your tenant are USDA program participants, or anticipate participation in USDA programs, you should request a certified wetland determination from the local office of the Natural Resources Conservation Service prior to starting work.

This letter contains an approved jurisdictional determination for your subject site, which is valid for 5 years from the date of this letter unless new information warrants a revision prior to the expiration date. If you object to this determination, you may request an administrative appeal under Corps regulations at 33 CFR Part 331. Enclosed you will find a Notification of Appeals Process (NAP) fact sheet and Request for Appeal (RFA) form. If you request to appeal this determination, you must submit a completed RFA form to the Southwest Division Office at the following address:



December 27, 2013

Mr. Derek St. John, P.E., CFM Lockwood, Andrews & Newnam, Inc. 2925 Briarcark, Suite 400 Houston, TX 77042

Re: W140-01-00 Modification by TIRZ 17

Dear Mr. St. John:

This letter is in response to e-mail correspondence of December 12, 2013 wherein you provided me a summary of three options you have been discussing with both our Watershed Management Department and also our Urban Channel Design planning committee. As I understand your concern, you are hesitant to proceed with detailed impact analysis and any form of a project development report without some confirmation from Flood Control District that the hydraulic section you are presenting would be acceptable for maintenance. Three options have been presented, being combinations of multiple box culverts and concrete open channel. You are, at this time, recommending multiple box culverts from Gessner Road to Bunker Hill Road and an open concrete vertical wall section from Bunker Hill Road to an existing detention basin owned by TIRZ 17. In that recommended section you have 12 ft. maintenance berms on either side of the box culverts and maintenance berms of 15 ft. and 10 ft. on either side of the concrete channel section.

The idea that the channel sections being proposed depart significantly from the sections outlined in the Flood Control District Policy, Criteria and Procedures Manual (PCPM) is driven by the fact that acquisition of additional right-of-way is prohibitively expensive and disruptive to the community. We concur with this fact. The maintenance access widths are the minimum acceptable for our equipment based on the conceptual channel sections proposed. We will not accept anything less. We do not have adequate information to yet determine if the proposed design section meets our requirements for structural stability and hydraulic capacity which are studies you should undertake and provide as part of the impact analysis you intend to perform (including appropriate supporting field investigations). Of the conceptual sections provided we do want to offer the following comments.

For any modification to one of our channel reaches where we would replace an earthen section (or partial box section) with a full enclosure or concrete vertical wall, we would first want to attempt to maximize the capacity within the right-of-way for obvious difficulties in expanding the section in the future (given our requirements for maintenance access). It appears your conceptual sections do that, but please confirm such to be the case. If this is a case where additional capacity could be achieved if additional mitigation were available, we would like to understand that and determine if there is a partnership role the Flood Control District should take based on the benefit to the community. Any partnership would be a function of funding and Commissioners Court approval.

A Division of Harris County Public Infrastructure Department

MAR 0 6 2013

Preliminary Report Submitted on 12/31/2013





Fiscal Year Budget Comparisons

Description	2013	2014	2015
Planning and Design	\$ 700,000	\$ 699,000	\$ 1,213,800
Acquisition	- 0 -	- 0 -	\$ 100,000
Construction	\$ 7,000,000	\$ 7,000,000	\$ 12,000,000
Other	- 0 -	\$ 100,000	- 0 -
Total	\$ 7,700,000	\$ 7,799,000	\$ 13,313,800

W-140 Channel Improvements Timeline

Task Name	Duration	Start	Finish	2014 2015 2016 2017 Otr 1 Otr 2 Otr 3 Otr 4 Otr 2 Otr 3 Otr 4 Otr 1
Authorization to Proceed	0 days	Tue 2/25/14	Tue 2/25/14	2/25
Detailed Design	180 days	Wed 2/26/14	Sun 8/24/14	Detailed Design
ROW Acquisition	120 days	Thu 6/26/14	Thu 10/23/14	ROW Acquisition
Approvals	60 days	Mon 8/25/14	Thu 10/23/14	Approvals
Bidding	60 days	Mon 8/25/14	Thu 10/23/14	Bidding
Construction	540 days	Fri 10/24/14	Fri 4/15/16	Construction
Completion	0 days	Fri 4/15/16	Fri 4/15/16	4/15

W-140 Channel Improvements CIP Number T-1734



Presented to the Board of Directors February 25, 2014